



Doc. No.: STPL/RF/05/spl

Page 1 of 1

Ref: STPL/Tiles/JO – 293/12/ 2021.4

Test Order dated: 18.12.2021

Date: 31.12.2021

M/s. Sinter Machines
35, Peelamedu Industrial Estate,
V K Road, Peelamedu, Coimbatore
Tamilnadu – 641 004

REPORT ON ROOF TILE SAMPLE

Source of sample : Sample supplied by the customer
Date of receipt of sample : 15.12.2021
Customer's Reference : E mail dated 21.12.2021
Period of Test : 27.12.2021
Product Description# : Roof Tile – HR 1, HR 2, HR 3
Condition of samples : Satisfactory

Sl. No.	Test Conducted	Test Method	Test Result
1	Heat Resistance – 50°C for 4 hours	Kept in oven at 50°C for 4 hours and observation made	No change in volume and mass observed & No deformation observed
2			No change in volume and mass observed & No deformation observed
3			No change in volume and mass observed & No deformation observed

As furnished by the customer

- Note:
1. The results relate only to the items tested.
 2. Report shall not be reproduced, except in full, without the written approval of the lab.
 3. Any correction invalidates this report.

for STEDRANT TECHNOCLINIC PVT. LTD.

Radhakrishna
31/12/2021

 **Radhakrishna**
STPL Manager-Lab